

# Home Project Timeline

## A resource by Honest Abe Log Homes



The order of the steps contained in this guide may vary by project, but overall, should provide a look at the most common necessary steps. It is suggested that you speak with your General Contractor about the details of each.

Honest Abe Log Homes  
[www.honestabe.com](http://www.honestabe.com)

All log or timber home construction follows the same basic steps. This timeline details the events that will occur as you build your new home.

### Pre Construction Steps

- Gather design ideas.
- Visit log home models, tours and events.
- Purchase land to build on.
- Preliminary budgeting.
- Select log or timber frame manufacturer.
- Develop preliminary plans.
- Select General Contractor / subs.
- Arrange for financing.
- Preliminary construction schedule.
- Finalize plans
- Order package from log or timber company.
- Arrange for builders risk insurance.
- Apply for permits.
- Finalize bids from GC or subs.
- Finalize financing.
- Arrange for temp electricity.
- Give notice of start.
- Break ground!



Many of the steps listed here are carried out by the General Contractor. We have included them for educational purposes. Although not all items are applicable to all homes and situations, we hope that this will serve as a useful guide and educational tool as you prepare to build your own log or timber frame home.

Honest Abe Log Homes  
[www.honestabe.com](http://www.honestabe.com)

Copyright 2016, Honest Abe Log Homes,  
 In. All Rights Reserved

## Construction Site Prep

- Cut or grade entrance road or driveway. Clear site.
- Excavate basement.
- Water. Well or public.
- Install septic and drain field.
- Install temp toilet facilities.
- Locate and dig footings and pier pads.

## Dry-In Construction

- Confirm delivery date of home package.
- Confirm amount due on delivery.
- Prepare material storage area.
- Prepare for off-loading of material package.

## After Dry-In (Outside)

- Apply exterior treatment, stain and sealer.
- Install finished roofing.
- Install porch railings.

## After Dry-In (Inside)

- Erect fireplace and chimney.
- Rough in plumbing, HVAC, electrical service.
- Call for inspections of mechanicals and framing.
- Install ceiling, gable end and wall insulation if applicable.
- Install covering for interior partitions and ceilings.
- Apply paint, stain, wallpaper, etc.
- Install hardwood flooring, tile, carpet, etc.

## Final Inspections

- Inspect all work and make a punch list of corrections and oversights.
- Re-inspect after punch list complete.
- Obtain lien waivers.

- Call for footing inspection.
- Pour footings and pier pads.
- Treat site for termite prevention.
- Install foundation walls.
- Back-fill around facilities.
- Notify log or timber home representative of foundation completion.

- Check materials against shipping manifest.
- The home package should be constructed to dry-in completion by the log and timber home company or by your own labor source.
- Electrician should be on-site before log erection to mark electrical chase locations so the dry-in crew can drill as needed.

- Install garage doors.
- Install gutter and down spouts.
- Finish grading, top soil, seeding, sodding, shrubbery, etc.

- Install interior doors and hardware.
- Install interior window, door, baseboard and ceiling trim.
- Install cabinets and countertops.
- Install vanities, bars, mirrors, etc.
- Install closet shelving, poles, etc.
- Install stair treads, railings, balusters.
- Install tub and shower doors.
- Install plumbing fixtures and appliances.
- Install final HVAC and test.
- Install electrical fixtures, appliances, outlet covers, etc.

- Call for final inspections.
- Obtain occupancy permit.
- Notify financial institution of completion.
- Notify insurance company of completion.

**Enjoy your new log or timber frame home!**

